MIDDLE ST. CROIX WATERSHED MANAGEMENT ORGANIZATION

 455
 HAYWARD
 AVE.
 N.

 OAKDALE,
 MINNESTOA
 55128

 Phone
 651.330.8220
 x22
 fax
 651.330.7747
 www.mscwmo.org

PROJECT REVIEW

MSCWMO Project Review ID:

Project Name:

Applicant:

Purpose:

Location:

Review date:

Recommendation:

Applicability:

- Any project undertaking grading, filling, or other land alteration activities that involve movement of 100 cubic yards of earth or removal of vegetation on greater than 10,000 square feet of land
- Any project that creates or fully reconstructs 6,000 square feet or more of impervious surface
 - All major subdivisions or minor subdivisions that are part of a common plan of development. Major subdivisions are defined as subdivisions with 4 or more lots.
- Any project with wetland impacts
- Any project with grading within public waters
- ____ Any project with grading within buffers
- Any project with grading within 40-feet of the bluff line
- Development projects that impact 2 or more of the member communities
- New or redevelopment projects within the St. Croix Riverway that require a building permit that adds five hundred (500) square feet or more of additional impervious surface
- Any project requiring a variance from the current local impervious surface zoning requirements for the property





Any land development activity, regardless of size, that the City determines is likely to cause an adverse impact to an environmentally sensitive area or other property, or may violate any other erosion and sediment control standard set by the member community.
TAL ITEMS: nic submittals are highly encouraged
A completed and signed project review application form and review fee
Grading Plan/Mapping Exhibits
a. Property lines and delineation of lands under ownership of the applicant.
b. Delineation of existing on-site wetlands, shoreland and/or floodplain areas (including any buffers).
c. Ordinary High Water (OHW) elevations and datum, as determined by the MDNR (if applicable).
d. Existing and proposed site contour elevations related to NAVD 1988 datum (preferred) or NGVD, 1929. Datum must be noted on exhibits.
e. Drainage easements covering land adjacent to ponding areas, wetlands, and waterways up to their 100-year flood levels and covering all ditches and storm sewers. Access easements to these drainage easements and to other stormwater management facilities shall also be shown.
f. Minimum building elevation for each lot.
g. Identification of downstream water body.
Permanent Stormwater Management System in compliance with the requirements of the NPDES SDS Construction Stormwater Permit and MSCWMO Performance Standards.
a. Impervious areas (Pre- and Post-Construction).
b. Construction plans and specifications for all proposed stormwater management facilities.
c. Location(s) of past, current or future onsite well and septic systems (if applicable).
Other exhibits required to show conformance to these Performance Standards
A Stormwater Pollution Prevention Plan in compliance with the requirements of the NPDES SDS Construction Stormwater Permit
Grading Plan/Mapping Exhibits:
a. Delineation of the subwatersheds contributing runoff from off-site, proposed and existing on-site subwatersheds, and flow directions/patterns.
b. Location, alignment, and elevation of proposed and existing stormwater facilities.
c. Existing and proposed normal water elevations and the critical (the highest) water level produced from the 100-year 24-hour storms.
d. Location of the 100-year flood elevation, natural overflow elevation, and lowest floor elevations.

Middle St. Croix Watershed Management Organization

MEMBER COMMUNITIES: Afton, Bayport, Baytown Township, Lakeland, Lakeland Shores, Lake St. Croix Beach, Oak Park Heights, St. Mary's Point, Stillwater and West Lakeland Township

a. All hydrologic and hydraulic computations completed to design the proposed stormwater management facilities shall be submitted. Model summaries must be submitted. The summaries shall include a map that corresponds to the drainage areas in the model and all other information used to develop the model.

b. A table (or tables) must be submitted showing the following:

i. A listing of all points where runoff leaves the site and the existing and proposed stormwater runoff rates and volumes.

ii. A listing of the normal water levels under existing and proposed conditions and the water levels produced from the storm and runoff events listed above for all on-site wetlands, ponds, depressions, lakes, streams, and creeks.

Dedications or easements for the portions of the property which are adjacent to the facility and which lie below the 100 year flood level. For sites within public right-of-way, no easement is required.

A proposed maintenance agreement, which may be in the format of Appendix K, or other form approved by the city.

HISTORY & CONSIDERATIONS:

SPECIAL OR IMPAIRED WATER

This site drains to, and is within one mile of special or impaired water and complies with enhanced protections.

a. Scenic or Recreational river C.1., C.2., C.3.

b. Scientific and Natural area C.1., C.2., C.3.

c. Waterbody with a TMDL C.1., C.2.

C.1. Stabilization initiated immediately and all soils protected in seven days/provide temp basin for five acres draining to common location.

C.2. Treat water quality volume of one inch of runoff by retaining on site unless not feasible due to site conditions (See Part III.D.1. design requirements).

C.3. Maintain buffer zone of 100 linear feet from Special Water.

EROSION AND SEDIMENT CONTROL [A checked box indicates compliance]

A Stormwater Pollution Prevention Plan (SWPPP) that meets the National Pollutant Discharge Elimination System (NPDES) requirements.

Narrative

Identify the person knowledgeable and experienced who will oversee the implementation of the SWPPP; the installation, inspection, and maintenance of the BMPs.

a. Identifies the person who will oversee the BMP inspection and maintenance.

Middle St. Croix Watershed Management Organization

MEMBER COMMUNITIES:

Afton, Bayport, Baytown Township, Lakeland, Lakeland Shores, Lake St. Croix Beach, Oak Park Heights, St. Mary's Point, Stillwater and West Lakeland Township

b. Identify the training requirements are sat	isfied.
---	---------

- c. Inspections performed once every 7 days.
- d. Inspections performed within 24 hours of a rain event greater than 0.5 in/24 hours.
- e. Inspection and Maintenance records include:
 - i. Date and time of inspection.
 - ii. Name of person(s) conducting inspections.
 - iii. Finding of inspections, including the specific location where corrective actions are needed.
 - iv. Corrective actions taken (including dates, times, and party completing maintenance activities).
 - v. Date and amount of rainfall events greater than 0.5 in/24 hours.

vi. Rainfall amounts must be obtained by a properly maintained rain gauge installed onsite, or by a weather station that is within one mile or by a weather reporting system.

vii. Requirements to observe, describe, and photograph any discharge that may be occurring during the inspection.

viii. All discovered nonfunctional BMPs must be repaired, replaced, or supplemented with functional BMPs within 24 hours after discovery, or as soon as field conditions allow.

- Describes procedures to amend the SWPPP and establish additional temporary ESC BMPs as necessary for site conditions.
- Describes the installation timing for all Erosion Sediment Control (ESC) Best Management Practices (BMPs).
- Describes final stabilization methods for all exposed areas.
- Methods used to minimize soil compaction and preserve topsoil must be described.
- Describes dewatering technique to prevent nuisance conditions, erosion, or inundation of wetlands?
- NA Identifies any specific chemicals and the chemical treatment systems that may be used for enhancing the sedimentation process on the site, and how compliance will be achieved with the permit requirements.
 - Describes pollution prevention management measures
 - a. Storage, handling, and disposal of construction products, materials, and wastes.
 - b. Fueling and maintenance of equipment or vehicles; spill prevention and response.
 - c. Vehicle and equipment washing.
 - d. No engine degreasing allowed on site.
 - e. Containment of Concrete and other washout waste.
 - f. Portable toilets are positioned so that they are secure.

Middle St. Croix Watershed Management Organization

Plan sheets

NA Temporary Sediment Basins required (10 acres draining to common location or **5 acres** App. A) Basin design meets the following criteria:

- a. Adequately sized 2-year, 24-hour storm, minimum 1,800 feet/acre; or no calculative minimum 3,600ft3/acre.
- b. Designed to prevent short circuiting.
- c. Outlets designed to remove floating debris.
- d. Outlets designed to allow complete drawdown.
- e. Outlets designed to withdraw water from the surface
- f. Outlets have energy dissipation.
- g. Have a stabilized emergency spillway.
- h. Situated outside of surface waters and any natural buffers.
- Locations and types of all temporary and permanent Erosion Control BMPs.
 - a. Exposed soils have erosion protection/cover initiated immediately and finished within 7 days.
 - b. Wetted perimeters of ditches stabilized within 200 feet of surface water within 24 hours.
 - c. Pipe outlets have energy dissipation within 24 hours of connecting.
 - Locations and types of all temporary and permanent Sediment Control BMPs.
 - a. Sediment control practices established on down gradient perimeters and upgradient of any buffer zones.
 - b. All inlets are protected.
 - c. Stockpiles have sediment control and placed in areas away from surface waters or natural buffers.
 - d. Construction site entrances minimize street tracking?
 - e. Plans minimize soil compaction and, unless infeasible to preserve topsoil.
 - f. 50 foot natural buffers preserved or (if not feasible) provide redundant sediment controls when a surface water is located within 50 feet of the project's earth disturbances and drains to the surface water.
- Tabulated quantities of all erosion prevention and sediment control BMPs.
- Stormwater flow directions and surface water divides for all pre- and post-construction drainage areas.
- Locations of areas not to be disturbed (buffer zones).
- Location of areas where construction will be phased to minimize duration of exposed soil areas.
 - Blufflines are protected from construction activities in urban (40 foot buffer) areas and rural areas (100-foot buffer).

Middle St. Croix Watershed Management Organization

MEMBER COMMUNITIES:

Afton, Bayport, Baytown Township, Lakeland, Lakeland Shores, Lake St. Croix Beach, Oak Park Heights, St. Mary's Point, Stillwater and West Lakeland Township

LAKE, STREAM AND WETLAND BUFFERS

- A buffer zone of unmowed natural vegetation is maintained or created upslope of all water bodies (wetlands, streams, lakes).
- A 50 foot natural buffer or (if a buffer is infeasible) provide redundant sediment controls when a surface water is located within 50 feet of the project's earth disturbances and stormwater flows to the surface water.
- NA If adjacent to a Special or Impaired Water an undisturbed buffer zone of not less than 100 linear feet from the special water is maintained both during construction and as a permanent feature post construction.

STORMWATER MANAGEMENT [A checked box indicates compliance]

Water quality treatment is provided prior to direct discharge of stormwater to wetlands and all other water bodies.

Rate and Flood Control Standards

- The peak rate of stormwater runoff from a newly developed or redeveloped site shall not exceed the 2-, 10-, and 100-year 24-hour storms with respective 2.8, 4.2, and 7.3-inch rainfall depths with MSCWMO approved time distribution based on Atlas 14 for existing and proposed conditions. The runoff curve number for existing agriculture areas shall be less than or equal to the developed condition curve number. The newly developed or redeveloped peak rate shall not exceed the existing peak rate of runoff for all critical duration events, up to and including the 100-year return frequency storm event for all points where discharges leave a site during all phases of development.
 - Predevelopment conditions assume "good hydrologic conditions" for appropriate land covers as identified in TR–55 or an equivalent methodology. Runoff curve numbers have been increased where predevelopment land cover is cropland:

Hydrologic Soil Group A: Runoff Curve Number 56 Hydrologic Soil Group B: Runoff Curve Number 70 Hydrologic Soil Group C: Runoff Curve Number 79 Hydrologic Soil Group D: Runoff Curve Number 83

- Computer modeling analyses includes secondary overflows for events exceeding the storm sewer systems level-of-service up through the critical 100-year event.
- NA In sub-areas of a landlocked watershed, the proposed project does not increase the predevelopment volume or rate of discharge from the sub-area for the 10-year return period event.
- Flowage easements up to the 100-yr flood level have been secured for stormwater management facilities (such as ditches and storm sewers).
 - Lowest floor elevations of structures built adjacent to stormwater management features and other water bodies are a minimum of two feet above the 100-year flood elevation and a minimum of two feet above the natural overflow of landlocked basins.

Middle St. Croix Watershed Management Organization

Volume Control Standards

Calculations/computer model results indicate stormwater volume is controlled for new development and redevelopment requirements per the MSCWMO Design Standards.

- 1. New Nonlinear Development 1.1" * new impervious surfaces
- 2. Reconstruction/Redevelopment Projects 1.1" * reconstructed impervious surfaces
- 3. Linear Projects 0.55" * new and/or fully reconstructed impervious surface and 1.1" from net increase in impervious area
- 4. Sites with Restrictions- flexible treatment options documentation has been provided.

Volume Retention Required (cu. ft.)	Volume Retent	tion Provided (cu. ft.)
	BMP	Volume
xx,xxx sf *1.1" = xxx cu. ft.	BMP #1	x,xx cu. ft.
xx,xxx sf *1.1" = x,xxx cu. ft.	BMP #2	x,xxx cu. ft.
	Total Proposed	x,xxx cu.ft.
Total Required x,xxx cu. ft.		

Flexible Treatment Options (when applicable)

- Applicant demonstrated qualifying restrictions as defined in Section 7.2.2 (4) of the 2015 MSCWMO Watershed Management Plan that prohibits the infiltration of the entire required volume.
- MIDS calculator submission removes 75% of the annual total phosphorous.

Infiltration/Filtration Design Standards

Proposed stormwater management features meet or exceed NPDES General Construction Permit requirements are designed in conformance with the most recent edition of the State of Minnesota Stormwater Manual.

None of the following conditions exist that prohibit infiltration of stormwater on the site

- a. Areas where vehicle fueling and maintenance occur.
- b. Areas with less than three (3) feet of separation distance from the bottom of the infiltration system to the elevation of the seasonally saturated soils or the top of bedrock.
- c. Areas where industrial facilities are not authorized to infiltrate industrial stormwater under an National Pollutant Discharge Elimination System (NPDES)/State Disposal System (SDS) Industrial Stormwater Permit issued by the MPCA.
- d. Areas where contaminants in soil or groundwater will be mobilized by infiltrating stormwater.
- e. Areas of Hydrologic Soil Group D (clay) soils
- f. Areas within 1,000 feet up-gradient, or 100 feet down-gradient of active karst features unless allowed by a local unit of government with a current MS4 permit.

Middle St. Croix Watershed Management Organization

Setback	Minimum Distance (ft)	
Property line	10	
Building foundation*	10	
Private well	35	
Public water supply well	50	
Septic system tank/leach field	35	
*Minimum with slopes directed away from the building		

] Minimum setbacks from the Minnesota Department of Health for infiltration practices are met

Pretreatment devices(s) remove at least 50% of sediment loads. If downstream from a potential hot spot, a skimmer is in place to facilitate cleanup.

Water quality volume will be discharged through infiltration or filtration media in 48 hours or less.

- a. For bioretention (biofiltration and bioinfiltration) volume control management facilities above ground with vegetation the period of inundation shall be calculated using the maximum water depth below the surface discharge elevation and the soil infiltration rate.
- b. For infiltration basin volume control management facilities the period of inundation shall be calculated using the maximum water depth below the surface discharge elevation and the soil infiltration rate.

Appropriate soil borings have been conducted that meet the minimum standards.

- a. A minimum of one boring was conducted at the location of the infiltration facility for facilities up to 1,000 ft²; between 1,000 and 5,000 ft², two borings, between 5,000 and 10,000 ft², three borings and greater than 10,000 ft² 4 borings plus an additional boring for every 2,500 ft² beyond 12,500 ft²
- b. Soil borings extend a minimum of five feet below the bottom of the infiltration practice. If fractured bedrock is suspected, the soil boring goes to a depth of at least ten feet below the proposed bottom of the volume control facility.

c. A minimum of three feet of separation to the seasonal water table and/or bedrock.

d. Identify unified soil classification.

] The least permeable soils horizon identified in the soil boring dictated the infiltration rate.

Additional flows are bypassed and are routed through stabilized discharge points.

Filtration basin demonstrates a basin draw down between 24 hours and 48 hours.

Filtration system Iron Enhanced Sand Filter is sized to bind soluble phosphorous removal for 30 year functional life of the system using the published value of 17lbs.phosphorous removal per 20 yards of 5% by weight iron filings to 95% sand.

Middle St. Croix Watershed Management Organization

MEMBER COMMUNITIES:

Afton, Bayport, Baytown Township, Lakeland, Lakeland Shores, Lake St. Croix Beach, Oak Park Heights, St. Mary's Point, Stillwater and West Lakeland Township

L Identify as build survey and method to demonstrate infiltration or filtration basin is functioning.

Construction plans provide adequate construction guidance to prevent clogging or compaction and demonstrate
performance.

- a. Excavation within 2.0 feet of final grade for infiltration/filtration systems is prohibited until contributing drainage areas are constructed and fully stabilized.
- b. Rigorous sediment and erosion controls planned to divert runoff away from the system.
- c. Installation of volume control facilities must occur in dry soil conditions. Excavation, soil placement and rapid stabilization of perimeter slopes must be accomplished prior to the next precipitation event.
- d. Excavation shall be performed by an excavator with a toothed bucket. Use excavator bucket to place materials. Construction equipment shall not be allowed into the basin.
- e. Prior to the release of any remaining fee or security, the permit holder must provide documentation that constructed volume control facilities perform as designed.
- L There is a way to visually verify the system is operating as designed.

A minimum 8.0' maintenance access is provided to all stormwater facilities.

WETLAND PERFORMANCE STANDARDS

- Direct discharge of stormwater to wetlands and all other water bodies without water quality treatment is prohibited.
- Any potential changes to the hydrology of the wetland (i.e. changes to the outlet elevation or contributing drainage area) must be reviewed to evaluate the impact of both the existing and proposed wetland conditions and approved by the MSCWMO.
 - Land-altering activities shall not increase the bounce in water level or duration of inundation from a 2.0-inch 24hour storm for any downstream wetland beyond the limit specified in Table 7.2 for the individual wetland susceptibility class.